



B-2 LEVEL REPLACEMENT QUANTITY SCHEDULE	
AREA	REPLACEMENT FIREPROOFING QUANTITY
SOUTH	524 SQUARE FEET OF FIREPROOFING

- NOTES**
1. FIREPROOFING MATERIAL SHALL BE HIGH DENSITY CEMENTITIOUS, THICKNESS SHALL PROVIDE THE FOLLOWING FIRE PROTECTION:
 - BEAMS 2 HRS.
 - COLUMNS AND GIRDERS 3 HRS.
 - DIAGONAL BRACING 3 HRS.
 2. PROVIDE UL TEST DATA FOR ALL SUBMITTED PRODUCTS AND THICKNESS.
 3. ALL STEEL MEMBERS ARE TO BE CONSIDERED "RESTRAINED" FOR UL DATA.

LEGEND	
	AREAS TO BE RE-FIREPROOFED